

In-situ concrete suspended ground floors

(August 2024) (Second issue – supersedes December 2008)

The Technical Guidance Notes are produced by NHBC as guidance solely for our builder customers as to how to interpret the technical requirements in relation to the warranty cover provided by NHBC under its Buildmark, Buildmark Choice, Buildmark Link, Buildmark Solo, Buildmark Connect or any similar product from time to time. It has not been created or intended for distribution or use outside of that purpose. The information contained in this Technical Guidance Note does not constitute advice and is not to be relied upon by any third party. Nothing in this Technical Guidance Note is intended to, nor should it be taken to, create any legal or contractual relationship. Any third party who chooses to rely upon the information contained in the Technical Guidance Notes shall do so entirely at their own risk and NHBC accepts no duty of care or liability, however caused, in connection with its use or reliance by any third party.

Question

- Where an in-situ concrete suspended ground floor is laid on a dpm, should the dpm be dressed up the side and over the slab (sketch A) or cut off at the bottom (sketch B)?
- Is it necessary to provide a dpc between the top of the slab and the masonry inner leaf?

Considerations

- Cutting the dpm off would leave the slab exposed to water, which may collect at the bottom of the cavity. This could cause dampness in the home.

Answer

- The dpm should be dressed up the side and over the slab (see sketch A). The dpm should be pulled taut so that it does not bulge and tend to form a ledge on which mortar could build up.
- A separate dpc is not required between the top of the slab and the inner leaf masonry where the dpm has been dressed up the side and over the slab.

